

# Kennington DWP –

## Boiler Works

Client: ISG Retail

Value: £150,000

Duration: 12 Weeks



Mectric Solutions Ltd

Mectric Solutions were appointed by ISG working with the Department of Work and Pensions, to carry out the installation of a new plant room at the Kennington Job Centre.



The existing plant, pipework, and wiring within the plant room were removed. New boilers, pumps and associated plant were then installed, along with new pipework and wiring inside the plant room.



The services comprised of:

- Removal of existing plant and pipework inside the plant room
- New heating system including boilers, pumps, and associated plant.
- New heating pipework including flow and return and low loss headers
- Pipework insulation
- Power and lighting
- BMS Controls
- New distribution board
- Water treatment and commissioning
- Provided temporary heating to the building

